

LAW OFFICES

**JENNER & BLOCK**

A PARTNERSHIP INCLUDING PROFESSIONAL CORPORATIONS

ONE IBM PLAZA

CHICAGO, ILLINOIS 60611

TELEPHONE (312) 222-9350

TWX 910-221-5409

TELEX 270469

CABLE JENBLOCK

TELECOPIER 527-0484

WASHINGTON OFFICE

21 DUPONT CIRCLE, N.W.

WASHINGTON, D.C. 20036

(202) 223-4400

LAKE FOREST OFFICE

ONE WESTMINSTER PLACE

LAKE FOREST, ILLINOIS 60045

(312) 295-9200

NORMAN W. BERNSTEIN

December 1, 1988

151819

CONFIDENTIAL FOR SETTLEMENT  
PURPOSES ONLY

By Messenger

Charles McKinley, Esq.  
Assistant Regional Counsel  
U.S. Environmental Protection Agency  
230 South Dearborn Street (5CS-TUB)  
Chicago, Illinois 60604

Re: Proposed Enviro-Chem Consent Decree

Dear Mr. McKinley:

As a follow up to the meeting which we had on November 12, 1988, I am enclosing herewith a revised draft of the Enviro-Chem Consent Decree.

The principal changes are as follows. The latest draft adds background information (pp. 4-5), the inter-relationship with the amendment to the ROD (p. 6), eliminates provisions on conveyance of the facility since Bankert will not be a party (pp. 12-13) and substitutes the Northside decree versions of force majeure (pp. 21-23) and stipulated penalties (pp. 27-34) with adjustments necessary to conform to the balance of the decree. Additionally, all references to the scope of work and work plan have been deleted and the neutral term "Appendix A" has been substituted.

The "X" version shows the changes from the preceding draft and the "Y" version is after giving affect to those changes.



**ERM-North Central, Inc.**

**Environmental Resources Management**

102 Wilnot Road • Suite 300 • Deerfield, Illinois 60015 ☎ (312) 940-7200

November 3, 1988

Elizabeth Maxwell  
Office of General Counsel  
U.S. Environmental Protection Agency  
Region V  
230 South Dearborn Street  
Chicago, IL 60604

RE: ECC Remedial Action Work Plan

Dear Ms. Maxwell:

As instructed by the ECC Steering Committee, enclosed please find one (1) copy of the Confidential Preliminary Draft for Settlement Purposes Only of the Remedial Action Work Plan for the Environmental Conservation and Chemical Corporation (ECC) site at Zionsville, Indiana

Very truly yours,

ERM-NORTH CENTRAL, INC.

*Roy Ball / ERM*

Roy O. Ball, Ph.D., P.E.  
Principal

jls

Enclosures

cc: M. Grummer  
K. Vendl ✓  
A. Sloan  
J. Buck  
D. Smith  
J. Amber  
N. Bernstein  
T. Harker

**CONFIDENTIAL PRELIMINARY DRAFT  
FOR SETTLEMENT PURPOSES ONLY**

**REMEDIAL ACTION WORK PLAN  
DETAILED ANALYSIS**

**ENVIRONMENTAL CONSERVATION AND  
CHEMICAL CORPORATION (ECC) SITE  
ZIONSVILLE, INDIANA**

**NOVEMBER, 1988**

**PREPARED FOR:**

**ECC SETTLERS STEERING COMMITTEE**

**PREPARED BY:**

**ENVIRONMENTAL RESOURCES MANAGEMENT-NORTH CENTRAL, INC.  
102 WILMOT ROAD, SUITE 300  
DEERFIELD, ILLINOIS 60015**

**PROJECT NO. 8076**

## TABLE OF CONTENTS

<u>Section</u>	<u>Title</u>	<u>Page No.</u>
LIST OF TABLES		
LIST OF FIGURES		
1.0	INTRODUCTION	1
2.0	SOIL VAPOR EXTRACTION, CONCENTRATION AND DESTRUCTION	3
3.0	SOIL COVER	9
4.0	DIVERSION OF SURFACE WATER RUNOFF UPGRADIENT OF CONCRETE PAD AND COLLECTION OF WATER FROM BENEATH THE CONCRETE PAD	11
5.0	SHALLOW SATURATED ZONE GROUND WATER INTERCEPTION AND COLLECTION	13
6.0	ACCESS RESTRICTIONS	15
7.0	GROUND WATER AND SURFACE WATER MONITORING	16
8.0	SCHEDULE	19
APPENDIXES		

## LIST OF TABLES

<u>TABLE NO.</u>	<u>DESCRIPTION</u>	<u>FOLLOWING PAGE NO.</u>
1	Estimate of VOC Mass in the Soils	7
2	Calculation of Acceptable Remaining Soil Concentrations	8
3	Calculation of Travel Time in the Sand and Gravel Unit	17

## LIST OF FIGURES

<u>FIGURE NO.</u>	<u>DESCRIPTION</u>	<u>FOLLOWING PAGE NO.</u>
1	Remedial Action Plan Schematic	2
2	Vapor Extraction Trench Schematic	6
3	Cross-Section of Soil Cover	10
4	Surface Water Runoff Diversion Berm	11
5	Concrete Pad Drain	12
6	Ground Water Interception Trench	13
7	Geologic Cross-Section Illustrating Location of Ground Water Interception Trench	13
8	Potentiometric Surface Map of Upper Sand and Gravel Aquifer	17
9	Estimated Project Schedule	19

**REMEDIAL ACTION WORK PLAN  
DETAILED ANALYSIS**

**ENVIRONMENTAL CONSERVATION AND  
CHEMICAL CORPORATION (ECC) SITE  
ZIONSVILLE, INDIANA**

**1.0 INTRODUCTION**

This is a Remedial Action Work Plan (RAWP) for the ECC Site. The RAWP addresses all environmental concerns regarding the site, namely:

- o direct contact with soils containing volatile organics (VOCs), semivolatile organics, and heavy metals;
- o contamination of ground water by rain water percolating through soils containing VOCs, semivolatile organics, and heavy metals;
- o contamination of surface waters by overland migration of water in contact with soil containing VOCs, semivolatile organics, and heavy metals;
- o ingestion of ground water containing VOCs, semivolatile organics, and heavy metals; and

- o contamination of surface waters by discharge of ground water containing VOCs, semivolatile organics and heavy metals.

*as compared to what (delete)*

Additionally, the RAWP most closely complies with the Superfund Amendments and Reauthorization Act (SARA) of 1986 by removing VOCs from the soils and destroying them.


The RAWP includes the components listed below (Figure 1):

- o soil vapor extraction, concentration and destruction;
- o soil cover;
- o diversion of surface water runoff upgradient of concrete pad and collection of water from beneath the concrete pad;
- o shallow saturated zone ground water interception and collection;
- o access restrictions; and
- o ground water and surface water monitoring.

The following sections present for each component: (1) description and technical basis, (2) objectives, and (3) performance standards which would be utilized to evaluate their effectiveness. A schedule for implementation of the work plan is also presented.


Although the detailed design of the Northside Sanitary Landfill (NSL) remedial action plan has not been finalized, the plan





LEGEND:	
	BUILDING
	CONCRETE PAD
	FENCE
	BELOW GRADE PIPING
	COLLECTION MANIFOLD
	ECC SUMP LOCATION
	MONITORING WELL LOCATION
	SURFACE WATER SAMPLING POINT
	GRID POINT

NOTE: EXISTING SITE STRUCTURES ARE NOT SHOWN FOR THE SAKE OF CLARITY.



<b>ECC REMEDIAL ACTION PLAN SCHEMATIC</b>	FIGURE <b>1</b>
	10/27/88
	CS

*will phase be shown*

*How do you know this is better?*

presented herein is compatible with the proposed remedy for the NSL site. If necessary, modifications to the design will be done to merge both remedies appropriately.

## 2.0 SOIL VAPOR EXTRACTION, CONCENTRATION AND DESTRUCTION

### Objectives

- o remove and destroy existing VOCs from the soils (as provided herein) and thereby:
  - 1) prevent contact with contaminated soils, ~~if any~~;
  - 2) prevent migration of contaminants, ~~if any~~, from the soils to the ground water; and
  - 3) prevent migration of contaminants, ~~if any~~, from the ground water to the surface water.

### Description

Soil vapor extraction would remove existing VOCs from the soils by enhancing and accelerating volatilization.

To accomplish this, pipelines would be installed in trenches dug in the soils. The vacuum pressure developed by the extraction system will cause the VOCs in the soils to migrate to the pipelines and into the vapor treatment system. The vacuum is provided by a blower. The vapor treatment system would consist of preconcentration of the VOCs by adsorption on activated carbon and destruction of the VOCs by incineration.

The effectiveness of vapor extraction for VOC removal from the soils was demonstrated during a pilot test run by Terra Vac in June 1988 (Appendix A). The test showed an initial high VOC extraction rate of about 1.9 lb/d per foot of trench that decreased with time to a steady-state rate of about 0.25 lb/d per foot of trench.

Prior to startup of construction of the vapor extraction system, the following activities would be conducted:

- o level out the site's surface;
- o relocate movable objects;
- o provide three-phase, 440 volt electrical service;
- o construct a 20' x 20' concrete pad for the blower emission control system; and
- o mobilize a trailer and minor utilities.

The trenches would have the same cross-section as in the pilot test, i.e., a minimum of 1 foot in width and a total of 9 feet in depth. Under the concrete pad, the depth of the vapor extraction trench would be reduced to 5 feet, because the concentrations of compounds detected in the soils are below the acceptable remaining soil concentrations calculated below (see page 7).

As shown in Figure 1, the site has been divided into three separate areas based on the site dimensions. The layout of the vacuum extraction system is also presented in Figure 1. The Area 1 and Area 2 trenches would have a 35-foot separation, based on a radius of influence of 15 to 20 feet found during the pilot test

*What P&E  
↓ design  
549 yards* *new  
assume  
w/ work plan*

(Appendix A). The trench separation beneath the concrete pad would be 80 feet, assuming that the radius of influence would double in the subbase of the concrete pad, which has a higher permeability than the shallow till. The length of the trenches would be 150 feet, 100 feet and 200 feet in Areas 1, 2, and 3, respectively, based on the dimensions of each zone.

*which  
one?*

Trenches would be dug by a conventional backhoe using a narrow width bucket. The dirt would be placed directly in a lined, light dump truck and/or stockpiled for removal by a front-end loader. The excavated dirt would be placed in windrows on the existing concrete pad for subsequent vapor extraction (Area 3 on Figure 1) installing an extraction pipe at the bottom of the windrows and connecting it to the vapor extraction system. The trenches under the concrete pad would be laid on the pad's subbase and dug in a similar way. The concrete debris would be placed on top of the concrete pad and leveled out. A maximum of 1800 cubic yards is expected to be excavated during trench construction.

*what do  
you  
mean  
by  
this?*

*to where*

A 4-inch slotted PVC pipe would be placed at the 8-foot level within the trenches to drain off any ground water that may accumulate in the trenches. This pipe would be connected to a 4-inch PVC riser which would be manifolded at the surface and connected to a positive displacement pump for water removal and discharge to the ground water interception system.

The vapor extraction pipe would be located at the 6-foot level and would consist of 50 feet each of 6-, 8- and 10-inch slotted PVC pipe. The pipe size was selected to have a maximum velocity of 40 feet per second (fps) before transition to the next section. The pipe would be connected via a 10-inch riser to the surface for connection to the above ground vacuum manifold.


The trenches would be filled to the 5-foot level with pea gravel, which would be covered with a 30 mil or greater thickness polyethylene liner. A one-foot thick bentonite seal would be constructed on top of the liner using hydrated bentonite pellets. The trench would be filled to grade (approximately 4 feet) with a cement grout mixture and slightly mounded with native soil and visqueen membranes to prevent infiltration of surface water and vacuum breakthrough to the surface (Figure 2).

The vapor extraction trenches underneath the concrete pad would be modified as follows: (1) the water and vapor extraction pipes would be located at the 4-foot and 3-foot level, respectively; (2) the trench would be filled to the 2-foot level with pea gravel, covered with a 30-mil liner and filled to the one-foot level with a bentonite seal; and (3) the trench would be filled to grade and slightly mounded with a cement grout mixture.

The trench vapors would be collected in an above ground manifold. The manifold would be insulated and would change in size from 1' x 1.25' at the start of the manifold system to a nominal 3' x 3' at the connection to the blower plenum, to accommodate the increased flow of vapors. The blower plenum would be designed to receive 25,000 SCFM at a nominal 4' x 4' size. The surface manifold would be sloped to allow the removal of any condensation which may form. The water collected in the condensation trap would be combined with the water collected in the trenches and conveyed to the Indianapolis sewage treatment system (see Section 5).

The vapor extraction blower motor and control system would be capable of removing a nominal 25,000 SCFM against a resistance of 3" Hg (equivalent to about 400 HP). After initial extraction development during the pilot test, a steady-state soil resistance of 2-1/2" Hg was measured. Therefore, the piping and manifold system would be designed for a maximum resistance of 1/2" Hg (a

not described  
see  
Table  
F-2A



\* SIZE VARIABLE, DEPENDING ON  
LOCATION (SEE FIGURE 6)

NOTE: NOT TO SCALE

ECC REMEDIAL ACTION PLAN VAPOR EXTRACTION TRENCH SCHEMATIC	FIGURE 2
	10/27/88 CS
ERM North Central, Inc.	

higher vacuum). The controls would consist of motor control and starter with automatic shut-off in the event of: (1) excessive condensation in the vacuum system; (2) high or low suction pressure levels; and (3) failure of the VOC adsorption/concentration system.

The exhaust VOC adsorption/concentration system would collect the VOCs extracted from the soil and would consist of three 12-foot diameter unlined carbon steel vessels, each holding approximately 13,600 pounds of granular activated carbon. This is based on: (1) a flow rate of 25,000 SCFM; (2) concentrations of trichloroethylene (TCE) and 1,1,1-trichloroethane (TCA) in the vapors of 34 ppmv and 16 ppmv, respectively, as detected during the pilot test; (3) a carbon capacity for these two compounds of about 25% by weight; and (4) an assumed total mass of VOCs of about 5,500 pounds. This carbon system would be able to handle the entire mass of VOCs extracted from the soils during the remediation. Based on the soil samples collected during the RI, it was estimated that about 4,700 lb of VOCs were present in the soils (Table 1). Therefore, the amount of carbon in the system is about 20% more than the theoretical required amount.

After vapor extraction is completed, the spent carbon containing the extracted VOCs would be transported to a licensed off-site RCRA facility. At the facility, the VOCs would be stripped and destroyed and the carbon regenerated by high temperature incineration.

Samples of the extracted vapor and the exhaust vapor would be collected daily during the first week of operation, weekly for the following 4 weeks, and monthly thereafter. Samples would be analyzed for VOCs. Also, flow rate would be monitored and recorded, to provide enough data to calculate the mass of VOCs removed from the soils.

TABLE 1  
ECC REMEDIAL ACTION PLAN  
ESTIMATE OF VOC MASS IN THE SOILS \*

Location	Sampling depth ft	Assumed contamination depth, ft	Total VOCs concentration ug/kg	Mass of VOCs lb
TP-1	1 - 1.5	2	102	0.014
TP-2	1 - 1.5	2	28	0.004
TP-3	1 - 1.5	2	107,700	14.827
TP-4	1 - 2	2.5	97,330	16.749
TP-4	2.5 - 3.5	4	16	0.004
TP-5	1 - 2	2	22,587	3.109
TP-5	2 - 3	1.5	291	0.030
TP-6	1 - 2	2	10,505,000	1,446.173
TP-6	2 - 3	1.5	22,450	2.318
TP-6	4 - 5	1.5	16	0.002
TP-7	1 - 2.5	2.5	231,000	39.751
TP-7	2.5 - 4	2	279,200	38.436
TP-8	1 - 2.5	2.5	67	0.012
TP-8	2.5 - 4	2	315,600	43.447
TP-9	1 - 3	3	14,604,000	3,015.694
TP-9	3 - 5	2.5	130	0.022
TP-10	1 - 3	3	108	0.022
TP-10	3 - 5	2.5	92	0.016
TP-11	1 - 3	3	130	0.027
TP-11	3 - 5	2.5	67	0.012
TP-12	1 - 3	3	34,690	7.163
TP-12	3 - 5	2.5	3,609	0.621
SB-01	2.5 - 4	3	3,303	0.682
SB-02	2.5 - 4	3	12,900	2.664
SB-03	2.5 - 4	3	70,070	14.469
SB-04	2 - 3.5	2.5	175	0.030
SB-06	2 - 3.5	2.5	220,900	38.013
SB-08	2.5 - 4	3	3,012	0.622
SB-09	2.5 - 4	3	60,390	12.470
SB0104	5.5 - 7	2	27	0.004
SB0204	5.5 - 7	2	34	0.005
SB0403	5 - 6.5	2	51	0.007
SB0805	7 - 8.5	2	188	0.026
SB0904	5.7 - 7	2	8,069	1.111
TOTAL VOCs, lb				4,698.555

\* The area contaminated is assumed to be a 25'x25' square around each sampling location. TP = test pit; SB = soil boring.  
Soil concentrations from ECC RI.

↑ A1?



The time required for soil treatment has been estimated by calculating acceptable remaining concentrations using the procedures detailed in the Endangerment Assessment Section and Appendix E of the RI. Table 2 presents the maximum and average concentrations of indicator VOCs (TCE, tetrachloroethylene (PCE), chloroform and methylene chloride) as detected in the soil samples during the RI investigation. The values presented in Table 2 are very conservative considering that access restrictions would be maintained and a cover placed on the site.

At the acceptable concentrations presented in Table 2, leaching of the compounds, if any, to the ground water and subsequent transport to the surface water would result in a risk at least two orders of magnitude lower than the predicted risk shown in Table 6-13 of the RI.

As shown in Table 2, TCE and PCE are the most significant indicators. Therefore, only the time required to remove these two compounds was calculated. During the pilot tests (Appendix A), the steady state removal rates of trichloroethene and tetrachloroethene were 0.1 lb/day per foot of trench and 0.02 lb/day per foot of trench, respectively. Both compounds were detected at the highest concentration in trench TP-6, at a depth of 1-2 ft.

In order to estimate the duration of treatment, it was conservatively assumed that an area of 625 ft<sup>2</sup> around sampling locations has the same concentration of compounds, and therefore the mass of TCE at TP-6 is 660 lbs, and the mass of PCE at TP-6 is 90 lbs. For a 99.92% removal of TCE (Table 2), the current maximum mass would have to be reduced to 0.6 lb, which at a rate of 0.1 lb/day per foot of trench would take about 265 days (using a trench length of 25 ft crossing the area). Similarly, for PCE the required time would be about 180 days. If lower

TABLE 2

**ECC REMEDIAL ACTION PLAN  
CALCULATION OF ACCEPTABLE REMAINING SOIL CONCENTRATIONS  
BASED ON DATA AND METHODOLOGY IN THE ECC RI**

<u>Parameter</u>	<u>Compound (1)</u>			
	<u>TCE</u>	<u>PCE</u>	<u>CHLO</u>	<u>MECH</u>
Maximum concentration, ug/kg	4,800,000	650,000	2,900	310,000
Location of maximum concentration	TP6(1-2')	TP6(1-2')	SB02(2.5-4')	TP3(1-3')
Excess risk identified in Tables 2 and 4 of Appendix E of the ECC RI, maximum concentration (2)	1.2 E-3	3.0 E-4	2.6 E-6	2.5 E-6
Average concentration, ug/kg	354,300	52,900	370	32,800
Excess risk identified in Tables 2 and 4 of Appendix E of the ECC RI, average concentration (2)	8.8 E-5	2.4 E-5	3.4 E-7	2.7 E-7
Concentration for acceptable risk, calculated, (2) ug/kg	4,000	2,100	1,100	124,000
Required removal, %				
Maximum concentration	99.92	99.68	62	60
Average concentration	99.0	96.0	--	--

(1) TCE = Trichloroethene  
PCE = Tetrachloroethene  
CHLO = Chloroform  
MECH = Methylene Chloride

(2) Based on ingestion of 1 gram of soil per day by a 70 Kg person over a period of 70 years (an intake rate of 0.013 g/Kg/d).

AI ?

concentrations are present, the treatment duration would be reduced accordingly.

### Performance Standards

The vapor extraction system would have completed its task when:

- o the exhaust vapors contain less than 1 ppmv of VOCs; and
- o the average concentrations of TCE, PCE, chloroform and methylene chloride in the soils, as determined by vapor measurements and calculations, are reduced to the following levels: TCE - 4000 ug/kg; PCE - 2100 ug/kg; chloroform - 1100 ug/kg; and methylene chloride - 124,000 ug/kg.

← have #5 above this below beneath SVE system

use soil samples in addition to vials

### 3.0 SOIL COVER

#### Objectives

- o prevent human contact with remaining contaminated soil, if ~~any~~;
- o prevent contamination, if ~~any~~, of surface runoff;
- o reduce the infiltration of water through the soils; *if any*
- o promote evapotranspiration; *if any*

- o promote drainage of rain water away from the site; and *if any*
- o mitigate erosion. *if any*

### Description


The soil cover would consist of a 0.5 foot layer of the highly impermeable native soil, 60 mil HDPE plastic membrane and a 2-foot layer of top soil to support vegetation (Figure 3).

Prior to placing the soil cover, the site would be graded to fill existing depressions and eliminate sharp grade changes and would be sloped at about 1% to promote drainage. Vegetation to be established would be characterized by fibrous, shallow, laterally growing roots, such as grass.

The cover would be installed over all the site, after soil remediation is completed. Approximately 5300 cubic yards (cy) of native soils, 21,000 cy of top soil and about 23,000 square yards of plastic membrane would be required.

### Performance Standards

- o the inflow of ground water to the various interception trenches would be reduced as a result of decreased infiltration;
- o erosion would be minimal; and
- o a vegetative cover would be present over the site.



*Stage 2-4 9%  
Slope*

ECC REMEDIAL ACTION PLAN  
CROSS SECTION OF SOIL COVER

FIGURE  
3

ERM North Central, Inc.

10/27/88  
CS

#### 4.0 DIVERSION OF SURFACE WATER RUNOFF UPGRADIENT OF CONCRETE PAD AND COLLECTION OF WATER FROM BENEATH THE CONCRETE PAD


##### Objectives

- o prevent the infiltration of surface runoff beneath the concrete pad; *through*
- o eliminate the concrete pad subbase as a migration route for contaminants, if ~~any~~;
- o prevent contamination, if ~~any~~, of the saturated surface till beyond the concrete pad; and
- o collect the water, if ~~any~~, that may become contaminated through flow beneath the concrete pad. *- how will this happen - D-9 beneath pad is 10' deep*

##### Description

Surface water runoff from the northern part of the site largely flows south, where an existing berm along the north edge of the concrete pad redirects runoff to a drainage ditch west of the site. This berm would be repaired and/or reinforced to ensure that runoff cannot infiltrate beneath the concrete pad (Figure 4). This would essentially eliminate the generation of contaminated runoff into the USEPA - installed sump located at the south end of the pad. *purpose of berm, what about causing problems w/ cap on N side*

An estimated 0.1 gpm would be diverted by this system, assuming a drainage area equal to 1/2 of the northeastern section of the site would drain towards the concrete pad (approximately 20,800 ft<sup>2</sup>), a runoff coefficient of 0.1 and a precipitation rate of 40 in/year. *doesn't make sense*



NOTE: NOT TO SCALE

ECC REMEDIAL ACTION PLAN  
SURFACE WATER RUNOFF  
DIVERSION BERM

FIGURE

4

ERM ERM-North Central, Inc.

10/27/88

CS

Prior to placement of the soil cover, the diverted surface runoff would be conveyed to the Indianapolis Wastewater Treatment Plant. Subsequent to cover placement, surface water runoff would be directed, as storm water runoff, to Finley Creek.

*monitor this?*

In addition to the diversion of surface runoff, a lined collection trench approximately 4 feet deep by 1 foot in width would be installed along the south and southeast portions of the concrete pad (Figure 5). The trench would be sloped to the southeastern corner of the pad. The water collected from this trench will be analyzed periodically, as presented in Section 5.0. The water would then be mixed with the rest of the water from the site and conveyed to the Indianapolis sewerage system for final treatment.

*How long will this take to install? purpose of this trench?*

Once the surface water diversion system is installed, the amount of water flowing into this trench would be negligible. Initially, a flow of 0.6 gpm is estimated based on a precipitation of 40 in/yr, a 5% infiltration of rain water through cracks and around the edges of the pad, and a surface area of 27,300 ft<sup>2</sup>.

*Aug 24 memo says 0.06 gpm*

#### Performance Standards

- o minimal amounts of water would go beneath the concrete pad; and
- o contaminated water, if ~~any~~, infiltrating beneath the pad would be collected in the trench.

*needs to be measured*

*How to measure?*




N

directions?

road  
↓  
?

asphalt - how thick?  
work plan



NOTE: NOT TO SCALE

ECC REMEDIAL ACTION PLAN CONCRETE PAD DRAIN	FIGURE 5
	10/27/88 CS
ERM ERM-North Central, Inc.	

## 5.0 SHALLOW SATURATED ZONE GROUND WATER INTERCEPTION AND COLLECTION

### Objectives

- o collect contaminated ground water, if any, from the saturated till escaping removal by soil aeration.

### Description


The ground water interception system would consist of a french drain extending east-west south of the ECC site along the north side of the NSL access road (Figure 1). The road would remain open at all times during construction and later operation of the french drain system. The drain would be approximately 330 feet in length, 4 feet in width and would be variable in depth depending upon till thickness.

A schematic of the trench components is shown in Figure 6. A cross-section of the trench is presented in Figure 7.

A 4-in PVC perforated pipe would be installed at the bottom of the trench. Gravel would be used for backfilling the trench. A plastic liner would be installed in the south and lower boundaries of the trench to prevent collection of uncontaminated downgradient water (Figure 6).

The flow of water into the drain is estimated to be 0.70 gpm (Appendix B). Three components of flow were included: (1) regional ground water flow; (2) induced flow due to the trench; and (3) recharge due to precipitation and upward flow from the sand and gravel unit, which would be about 1 foot beneath the drain bottom.

ECC SITE



NOTE: NOT TO SCALE


ECC REMEDIAL ACTION PLAN  
GROUND WATER  
INTERCEPTION TRENCH

FIGURE  
6

**ERM** ERM-North Central, Inc.

10/27/88

CS



ADAPTED FROM: FIGURE 11A, CH2M-HILL, 1988  
DRAFT TECHNICAL MEMORANDUM NO. 2

GEOLOGIC CROSS-SECTION  
ILLUSTRATING LOCATION OF  
GROUND WATER  
INTERCEPTION TRENCH

FIGURE

7

ERM ERM-North Central, Inc.

10/27/88

CS

90" ungr. PVC pipe

The water collected in the french drain would then be conveyed to the Indianapolis sewerage system for final treatment.

Water from the ground water interception drain, the trench around the concrete pad and the vapor extraction system would be sampled and analyzed for the TCL parameters weekly, if possible, during the first 2 months after installation to determine the levels of contamination, if any, in the collected ground water. Afterwards, a monitoring program would be implemented according to the City of Indianapolis sewerage system requirements.

is there anything?

this should be spelled out  
this is supposed to be a work plan

The ground water interception trench would be operated during the same time as the vapor extraction system. After that, the need for continued operation of the interception trench would be assessed based on the volume and quality of the water collected compared to the associated risk, if any, using the methodology in the Endangerment Assessment for the site as presented in the RI.

no  
how  
this  
will

Performance Standards

- o prevent contamination, if any, attributable to the ECC site in the surface water south of the site; and
- o prevent contamination, if any, above endangerment levels in the sand and gravel unit beyond the interception trench.

collect contaminated ground water emanating from soil

## 6.0 ACCESS RESTRICTIONS

### Objectives

- o minimize contact with contaminated soils and water containing VOCs, semivolatile organics, and heavy metals; and
- o prevent further contaminant migration, ~~if~~ any, that could result from site excavation and development.

### Description

Access restrictions would consist of:

- o fencing around the site perimeter and posting of signs;
- o filing of appropriate restrictions with County registrar of deeds prohibiting usage of site for excavation and development;
- o filing of appropriate restrictions with County registrar of deeds prohibiting usage of ground water from the saturated till and the underlying sand and gravel; and
- o filing of appropriate restrictions with County registrar of deeds prohibiting installation of new water wells other than monitoring wells.

Ground water use restrictions would extend to areas where utilization of the shallow ground water would result in contamination, if any, being drawn to these locations.

Neither the saturated surface till nor the sand and gravel unit would predictably nor reliably support water supply development. Therefore, enforcing the restrictions on their use should not be difficult.

#### Performance Standards

- o the access restrictions to the site soils and ground water would be enforced by the appropriate County officials in accordance with prohibitions described above.

*do Co. officials enforce*

#### 7.0 GROUND WATER AND SURFACE WATER MONITORING

##### Objectives

- o detect VOCs migration, if any, to the ground water and surface water; and
- o detect VOCs in the sand and gravel unit, if any, that are not captured by the ground water interception system in the surface till.

*detect if remediation is working*

##### Description

The ground water monitoring network would consist of three (3) wells, which would be located downgradient of the southern limit of the ECC property and south of the Northside Sanitary Landfill (NSL) access road (Figure 1). These wells would be installed in

*check 10  
VOCs (Coulman)*

the sand and gravel unit underlying the saturated surface till. The wells would be 2-in PVC with an anticipated screen length less than or equal to 10 feet. If the sand and gravel unit intercepted by the boring is greater than 10 feet thick, the upper 10 feet would be screened. In cases where the sand and gravel is less than 10 feet thick, the entire sand and gravel interval would be screened.

The location of the monitoring wells is based on the ground water elevation contours shown in Figure 8. As part of the remediation of the NSL site, it is has been proposed that the Unnamed Ditch be isolated in a concrete conduit. Without the Unnamed Ditch as a discharge zone, ground water flow beneath the eastern side of the ECC site will be southerly. Therefore, monitoring wells located south of the site (Figure 1) are appropriate. *verify*

Samples from these wells would be collected quarterly during site soil remediation and analyzed for the parameters in the Target Compound List (TCL). Once the soil remediation is completed, monitoring will be continued for three (3) years, *minimum 5 yrs. probably more* on a semi-annual basis. Based on the distance to the monitoring wells, three (3) years will be sufficient time for any VOCs that escaped collection by vapor extraction to migrate from underneath the concrete pad to the wells in the sand and gravel unit (Table 3).

The indicator VOC of concern in the sand and gravel unit used for this analysis is trichloroethene (TCE). The travel time for this compound in this unit was estimated assuming a distance of 100 feet from the southern border of the concrete pad to the monitoring wells and permeabilities of  $10^{-3}$  -  $10^{-2}$  cm/sec. With the retardation factor calculated in Appendix C of the RI, the estimated time required for TCE to reach monitoring wells is 0.3-3 years (Table 3).

*TCE - 300 yrs  
to ditch what about  
northwest  
boundary for  
(refers to)  
S-13*

*this going  
to  
SVE system*



TABLE 3

ECC REMEDIAL ACTION PLAN  
CALCULATION OF TRAVEL TIME IN THE SAND AND GRAVEL UNIT  
BASED ON DATA AND METHODOLOGY IN THE ECC RI

<u>Parameter</u>	<u>TCE</u>
Retardation factor	3.2
Permeability of sand and gravel unit, cm/sec	$10^{-3} - 10^{-2}$
Ground water velocity, ft/yr	100 - 1,000
Distance to monitoring well from the concrete pad, ft	100
Travel time of compounds to monitoring well, yrs	0.3 - 3

(1) TCE = Trichloroethene

*Refer*




	FIGURE 8
ERM ERM-North Central, Inc.	10/27/88
	CS

*3 hours later  
upgraded  
sample  
in a culvert here*

The surface water would be monitored by sampling the Unnamed Ditch just south of the NSL access road (Figure 1). Surface water would be sampled at the same frequency as ground water and analyzed for the same parameters.

*WAD  
6/2/83*

The concentrations of TCE below which the monitoring would cease for the monitoring wells and the surface water sampling point are based on endangerment levels and the current historical data for the site. The threshold level of TCE for both the surface water sampling point and the monitoring wells would be 100 ug/l. The 100 ug/l level for the surface water sampling point is based on the concentration of TCE that would result in a  $6 \times 10^{-7}$  increased carcinogenic risk from wading in Finley Creek (Table E-14 of the RI). Using the same 100 ug/l value for the surface water sampling point and the monitoring wells is very conservative, since it assumes there is no dilution of surface water or ground water upon discharge to Finley Creek or Unnamed Ditch, respectively, in contrast to the 1:2 and 1:600 dilution ratios presented in Table 6-13 of the RI.

*NO*

*NO*

The monitoring would cease when the results for two (2) consecutive semi-annual sampling events, after the initial three (3) years of semi-annual sampling, are shown to be statistically significantly below these threshold values. Three (3) years is the longest calculated travel time to the monitoring point for the most significant indicator.

#### Performance Standards

- o monitoring wells should be operable at all times and inspected quarterly;
- o sampling should be conducted as specified; and

- o annual summary reports and an analysis of results from each sampling interval should be submitted to the USEPA. + the State

## 8.0 SCHEDULE

The estimated time required to complete design and implementation phases of the RAP is illustrated in Figure 9. This schedule is based on the number of weeks from a notice to proceed. Tasks to be conducted are:

- o soil vapor extraction:
  - 1) design/installation
  - 2) operation
- o soil capping
- o surface water diversion and collection of water from beneath the concrete pad
- o ground water interception
- o access restrictions
- o monitoring:
  - 1) installation
  - 2) sampling

Reports which will be prepared for USEPA review and comment are:


- o design document — when will this be submitted
- o monitoring well installation

QAPP  
sampling plan  
h+s plan

how about  
approval  
deadline?

— and state

**ESTIMATED PROJECT SCHEDULE**  
**ECC REMEDIAL ACTION WORK PLAN**  
**WEEKS FROM EFFECTIVE DATE OF PLAN APPROVAL**



\* SAMPLING WOULD BE CONDUCTED SEMIANNUALLY AFTER WEEK 104 FOR A MINIMUM OF 2.5 YEARS. SAMPLING AFTER THAT TIME WOULD BE AS DISCUSSED IN SECTION 7.0.

ECC SITE  
ESTIMATED  
PROJECT SCHEDULE

FIGURE  
9

**ERM** ERM-North Central, Inc.

11/3/88

CS

- o vapor extraction system installation
- o monthly progress reports during soil remediation
- o quarterly reports of results of analysis

**APPENDIX A**

**TERRA VAC PILOT TEST  
AT  
ENVIRONMENTAL CHEMICAL AND CONSERVATION CORP.  
ZIONSVILLE, INDIANA**

TERRA VAC PILOT TEST  
AT  
ENVIRONMENTAL CHEMICAL AND CONSERVATION CORP.  
ZIONSVILLE, INDIANA

INTRODUCTION

This report discusses the results of the vapor extraction pilot test conducted by Terra Vac with ERM-North Central at the Environmental Chemical and Conservation Corporation (ECC) NPL site in Zionsville, Indiana. The report discusses the major project activities, data gathered, and significant findings in the following sections:

- I. Summary
- II. System Installation
- III. Vapor Extraction Operations
- IV. Analytical QA/QC
- V. Projection of Clean-Up Time

I. SUMMARY

The vapor extraction pilot test was successful in demonstrating the Terra Vac Process as a technically sound and cost effective method for removing volatile organics from the ECC site soils. Horizontal extraction wells were shown to be superior to vertical extraction wells for the site geology. Clean up time for the site using vapor extraction was estimated to be 300-400 days.

During Terra Vac's pilot test and operating period, approximately 548 pounds of VOCs were removed from the soil at the site. Tests show an approximate 20 foot radius of influence for horizontal



extraction wells. The extended run time on HEW-2 developed the data necessary to project clean up time. The vapor extraction operations began on June 13 and continued, with only minor shut downs, until July 20.

## II. SYSTEM INSTALLATION

During the week of June 1, Terra Vac personnel arrived on site to receive and procure materials for the job. Trenching began on June 7 and continued until June 8. Subsurface vapor monitoring wells and Vertical Extraction Well (VEW-1) were installed during the remainder of the week. Following extraction trench installation, the major components of the extraction system were manifolded together. Figure 1 is a drawing showing the layout of the test site.

During trench installation soil samples were taken and analyzed for VOCs using the headspace method. As expected, the VOC concentration was highly variable over the length of the trench. Table 1 is a summary of the chemical analyses of the soil samples.

## III. VAPOR EXTRACTION OPERATIONS

Appendix A is a daily summary of the system and the operation of each well. Appendix B contains operating and analytical data taken during the pilot test.

### A. Well Development

HEW-2 was initially developed for 22 hours. The results of the development period showed high VOC extraction rates and a radius of influence extending to approximately 15 feet. Following

development of HEW-2, vapor extraction from HEW-1 and VEW-1 was initiated as a combined development. The combined development continued for approximately four more days. The results of that development period indicated that HEW-1 had lower VOC extraction rates than HEW-2 but a comparable radius of influence. However, no significant radius of influence was measured from the vertical extraction well (VEW-1).

## B. Operations

Figure 2 is a plot of the Cumulative Pounds of VOC Extracted by the System versus Run Time. Approximately 548 pounds of VOC were removed from the soil at the site during Terra Vac's operations. After well development, operations focussed on HEW-2, where VOC concentrations were expected and found to be highest. HEW-2 remained in operation for a total of 31.4 days, with a total of 470.8 pounds of VOCs removed, as shown in Figure 3. The radius of influence stabilized at 15 to 20 feet.

Figure 4 and 5 show cumulative VOCs removed from HEW-1 and VEW-1. The short run times reflect both the slow development of VEW-1 and the decision to operate HEW-2 solely. Following development, the unexpectedly high flow rates from HEW-2 necessitated its solo operation so that the pilot system's effectiveness could be maximized.

Figure 6 shows HEW-2 VOC removal rates vs. run time. This type of curve is consistent with Terra Vac's previous experience. Early high rates decline to a relatively stable removal rate that slowly decreases (spikes before day 10 were caused by optimization procedures or short term shutdowns). Figure 7, showing initial and final rates for the major contaminants at HEW-2, indicates how these changes in VOC removal rate occur. There are substantial drops in rates from beginning to end for the more volatile components such as DCE, TCA, and TCE, while

rates for Toluene, PCE, and Xylenes have changed little or increased. The Total VOC Removal Rate dropped by 87% from its high point of 76 lb/day to a low point of 9.9 lb/day when the system was shut off.

The extracted VOCs were exhausted using a dispersion stack with agreement from the Indiana Department of Environmental Protection. Air quality testing was performed at the site boundary by ERM-North Central using a hand held vapor analyzer with a photoionization detector. At no time did concentrations of the indicator compounds at the site boundary exceed allowable limits.

#### IV. ANALYTICAL QA/QC

Several attachments (1-4) are included in this report that outline GC parameters, sampling and QC procedures. Vapor analyses were by direct injection of samples into a Shimadzu GC-9A gas chromatograph equipped with a flame ionization detector and utilizing a capillary column for separation of the compounds. Calibration checks or recalibrations were done daily, prior to sampling. All sample syringes were air purged via pump, with several blanks run to verify efficiency of purging procedure. Questionable results (i.e., an unusual change in concentration) was cause to run a syringe blank and resample to verify initial analysis.

#### V. PROJECTION OF CLEAN-UP TIME

Based upon data collected from the operation of HEW-2, the clean-up time for the site using vapor extraction technology is projected to be approximately 350 days.


TABLE ONE

ECC SOILS DATA  
TERRA VAC PILOT TEST

HEW-1 SOIL SAMPLE ID	HEW-1 DEPTH FT.	HEW-1 DCE ppm	HEW-1 TCA ppm	HEW-1 BZ ppm	HEW-1 TCE ppm	HEW-1 TOL ppm	HEW-1 PCE ppm	HEW-1 mp-XYL ppm	HEW-1 TOTAL ppm
===== SOIL CONCENTRATION (PPH) =====									
T1-3-3	3.0	.2	3.2	NA	7.7	1.9	4.5	1.9	19.4
T1-6-7	7.0	.4	2.4	NA	4.5	2.1	9.6	2.2	9.4
T1-6-9	9.0	.1	.0	NA	.0	.0	.1	.0	.2
T1-12-4	4.0	2.4	59.6	NA	99.7	5.1	187.5	2.3	166.7
T1-12-7	7.0	4.5	63.9	NA	125.0	5.9	155.2	2.2	199.3
T1-20-2	2.0	6.8	18.3	NA	59.0	10.6	2.4	2.9	94.5
T1-25-7	7.0	3.9	8.8	NA	24.5	4.0	11.5	1.7	41.1
T1-35-5	5.0	7.7	45.6	NA	7.9	4.6	4.0	1.8	65.7
T1-35-6	6.0	62.3	96.2	NA	49.7	9.4	103.1	3.8	217.6
T1-40-3	3.0	6.3	4.3	NA	2.0	.5	1.6	.2	13.1
T1-40-5	5.0	1.5	22.4	NA	2.6	1.0	1.1	.5	27.5
T1-40-7	7.0	.7	67.4	NA	9.0	6.9	1.9	.6	84.1

HEW-2 SOIL SAMPLE ID	HEW-2 DEPTH FT.	HEW-2 DCE ppm	HEW-2 TCA ppm	HEW-2 BZ ppm	HEW-2 TCE ppm	HEW-2 TOL ppm	HEW-2 PCE ppm	HEW-2 mp-XYL ppm	HEW-2 TOTAL ppm
===== SOIL CONCENTRATION (PPH) =====									
T2-5-3	3.0	.6	3.6	NA	6.5	3.3	1.5	2.3	14.0
T2-5-7	7.0	1.1	180.8	NA	10.6	19.7	4.9	8.8	212.1
T2-5-9	9.0	.2	5.1	NA	8.5	1.2	8.7	1.0	15.0
T2-15-2	2.0	1.5	109.6	NA	6.8	15.3	2.1	3.4	133.2
T2-15-8	8.0	1.1	83.0	NA	16.2	13.8	2.2	4.9	114.1
T2-18-5	5.0	1.1	40.2	NA	12.0	.8	1.9	.1	54.2
T2-22-3	3.0	.4	54.7	NA	20.1	4.0	4.7	1.8	79.1
T2-22-8	8.0	.1	1.8	NA	.7	.4	.2	.2	3.0
T2-35-3	3.0	1.6	37.9	NA	58.7	18.1	26.4	10.1	116.2
T2-35-4	4.0	.6	54.5	NA	333.9	25.5	35.0	6.4	414.4
T2-35-7	7.0	1.4	68.9	NA	71.3	19.2	20.6	13.7	160.7
T2-43-5	5.0	2.5	153.5	NA	24.8	13.3	5.6	5.8	194.1
T2-45-2	2.0	.9	68.9	NA	21.7	12.5	3.8	4.1	103.9
T2-45-6	6.0	1.6	116.8	NA	15.4	14.1	2.5	4.6	147.8

⊕ KVM-7



ECC SITE  
SOIL VAPOR EXTRACTION SYSTEM  
PILOT TEST LAYOUT

FIGURE  
1

ERM ERM-North Central, Inc.

mo

# TOTAL LBS VOC REMOVED

## TERRA VAC - ECC PILOT TEST




FIGURE 2

HEW-2 LBS VOC REMOVED  
TERRA VAC HORIZONTAL EXTRACTION WELL




FIGURE 3

HEW--1 LBS VOC REMOVED  
TERRA VAC HORIZONTAL EXTRACTION WELL





FIGURE 4



FIGURE 5

VEW-1 LBS VOC REMOVED  
TERRA VAC VERTICAL EXTRACTION WELL



# HEW-2 VOC REMOVAL RATES TERRA VAC HORIZONTAL EXTRACTION WELL




FIGURE 6

# HEW-2 INITIAL & FINAL RATES TERRA VAC HORIZONTAL EXTRACTION WELL




FIGURE 7

**APPENDIX A**

TERRA VAC/ ECC - ERM SITE / PROJECT 88-304

XX SUMMARY - ECC VACUUM EXTRACTION PILOT TEST													
XX													
SAMPLE TIME		XX	X										
		XX	RUN X	FLOW	DCE	TCA	TCE	TOL	PCE	XYL	OTHER	T.VOC	CUH
		XX	TIME X	RATE	RATE	RATE	RATE	RATE	RATE	RATE	RATE	RATE	VOC
DATE	HRS MIN	XX	(DAYS)X	(SCFM)	(#/DY)	(#/DY)	(#/DY)	(#/DY)	(#/DY)	(#/DY)	(#/DY)	(#/DY)	(LBS)
14-Jun 12	17	XX	.00 X	0	0	0	0						0
14-Jun 12	18	XX	.00 X	4	.9	6.4	6.3	.5	1.1	.1	2.9	18.2	
14-Jun 12	38	XX	.01 X	4	.8	10.4	4.7	.7	.7	.1	3.0	20.5	
14-Jun 13	18	XX	.04 X	4	.9	10.3	4.3	.7	.9	.2	1.9	19.2	1
14-Jun 13	31	XX	.05 X	4									1
14-Jun 14	31	XX	.05 X	4									1
14-Jun 15	31	XX	.09 X	4	.7	11.5	4.7	.9	.9	.2	1.5	20.4	1
14-Jun 15	40	XX	.10 X	4									2
14-Jun 16	29	XX	.10 X	4									2
14-Jun 17	29	XX	.14 X	8	1.1	20.7	9.7	1.9	2.1	.6	2.7	38.7	2
14-Jun 20	42	XX	.28 X	8	.8	14.2	8.8	1.6	1.9	.5	2.1	30.1	7
15-Jun 8	39	XX	.77 X	17									22
15-Jun 9	20	XX	.77 X	17									22
15-Jun 11	30	XX	.86 X	17	1.0	15.5	13.4	2.2	3.0	.8	2.6	38.5	24
15-Jun 12	10	XX	.89 X	16								38.5	25
15-Jun 12	23	XX	.90 X	21	3.2	8.0	13.8	.3	1.4		.7	66.1	25
15-Jun 12	27	XX	.90 X	23	.8	2.9	1.5	.1	2.1		1.5	75.1	25
15-Jun 14	50	XX	1.00 X	38	1.3	9.4	5.3	1.0	4.1	.4	2.7	62.8	32
15-Jun 15	55	XX	1.05 X	41	.8	11.3	10.6	1.7	2.4	.5	2.1	53.6	35
15-Jun 16	2	XX	1.05 X	59								53.6	35
16-Jun 10	48	XX	1.83 X	79								53.6	77
16-Jun 13	6	XX	1.93 X	84	1.6	16.6	15.3	2.5	5.3	.8	3.4	45.5	82
16-Jun 15	45	XX	2.04 X	86								45.5	87
16-Jun 16	30	XX	2.07 X	98								45.5	88
16-Jun 19	15	XX	2.07 X	121									88
17-Jun 10	45	XX	2.72 X	191	2.9	23.5	24.4	3.2	8.6	1.0	12.3	75.9	113
17-Jun 11	0	XX	2.73 X	0	1.1	6.3	3.6	.5	3.4	1.0	12.3	75.9	114
17-Jun 11	40	XX	2.73 X	0									114
17-Jun 15	0	XX	2.87 X	202	.7	14.2	14.2	2.1	6.7	.6	3.4	41.9	116





A4

[illegible]



TERRA VAC/ ECC - ERM SITE / PROJECT 88-304

XX HORIZONTAL EXTRACTION WELL - HEW-1														HEW-1
XX														
SAMPLE TIME XX <<< OPERATING SUMMARY >>>														
XX RUN FLOW TOTAL DCE TCA TCE TOL PCE XYL OTHER T.VOC CUM														
XX TIME RATE VOC RATE RATE RATE RATE RATE RATE RATE RATE RATE RATE VOC														
DATE	HRS	MIN	XX	(DYS)	(SCFM)	(mg/l)	(#/DY)	(#/DY)	(#/DY)	(#/DY)	(#/DY)	(#/DY)	(#/DY)	(LBS)
14-Jun 12	17	XX												
14-Jun 12	18	XX												
14-Jun 12	38	XX												
14-Jun 13	18	XX												
14-Jun 13	31	XX												
14-Jun 14	31	XX												
14-Jun 15	31	XX												
14-Jun 15	40	XX												
14-Jun 16	29	XX												
14-Jun 17	29	XX												
14-Jun 20	42	XX												
15-Jun 8	39	XX												
15-Jun 9	20	XX												
15-Jun 11	30	XX												
15-Jun 12	10	XX												
15-Jun 12	23	XX												.00
15-Jun 12	27	XX			2	58.74	.8	2.9	1.5	.1	2.1	1.47	8.9	
15-Jun 14	50	XX	.1	17	9.97		.9	5.2	2.3	.7	3.7	.3 1.70	14.8	1.2
15-Jun 15	55	XX	.1	17									14.8	1.9
15-Jun 16	2	XX	.2	25									14.8	1.9
16-Jun 10	48	XX	.9	33									14.8	13.5
16-Jun 13	6	XX	1.0	34	2.50		.5	2.8	1.2	.3	2.1	.1 .62	7.5	14.5
16-Jun 15	45	XX	1.1	34									7.5	15.4
16-Jun 16	30	XX	1.2	39									7.5	15.6
16-Jun 19	15	XX	1.2	52										15.6
17-Jun 10	45	XX	1.8	68	2.23		.8	4.6	1.9	.3	3.0	.1 3.00	13.6	20.0
17-Jun 11	0	XX	1.8		2.23		.8	4.6	1.9	.3	3.0	.1 3.00	13.6	20.1
17-Jun 11	40	XX	1.8											20.1
17-Jun 15	0	XX	2.0	82	1.78		.7	4.9	2.0	.4	3.6	.2 1.44	13.1	21.0

## A. L.

[illegible]

TEKRA VAC/ ECC - ERM SITE / PROJECT 88-304

XX VERTICAL EXTRACTION WELL - VE-1													VE-1
XXX OPERATING SUMMARY XXX													
SAMPLE TIME	RUN TIME	FLOW RATE	TOTAL VOC	DCE RATE	TCA RATE	TCE RATE	TOL RATE	PCE RATE	XYL RATE	OTHER RATE	T.VOC RATE	CUM VOC	
DATE	HRS	MIN	XX	(DYS)	(SCFH)	(mg/l)	(#/DY)	(#/DY)	(#/DY)	(#/DY)	(#/DY)	(#/DY)	(LBS)
14-Jun 12	17		XX										
14-Jun 12	18		XX										
14-Jun 12	38		XX										
14-Jun 13	18		XX										
14-Jun 13	31		XX										
14-Jun 14	31		XX										
14-Jun 15	31		XX										
14-Jun 15	40		XX										
14-Jun 16	29		XX										
14-Jun 17	29		XX										
14-Jun 20	42		XX										
15-Jun 8	39		XX										.00
15-Jun 9	20		XX										
15-Jun 11	30		XX										
15-Jun 12	10		XX										
15-Jun 12	23		XX		4	73.67	3.2	8.0	13.8	.3	1.4	.7	27.6 .1
15-Jun 12	27		XX		4								27.6 .2
15-Jun 14	50		XX	.1	4	25.36	.4	4.2	3.0	.4	.4	.1 1.0	9.5 2.0
15-Jun 15	55		XX	.2	8								9.5 2.5
15-Jun 16	2		XX	.2	8								9.5 2.5
16-Jun 10	48		XX	.9	13								9.5 10.0
16-Jun 13	6		XX	1.0	13	2.18	.1	1.0	.5	.3	.1	.5	2.5 10.5
16-Jun 15	45		XX	1.1	15								2.5 10.8
16-Jun 16	30		XX	1.2	15								2.5 10.9
16-Jun 19	15		XX	1.2	15								10.9
17-Jun 10	45		XX	1.8	17	3.31	.3	1.7	1.7	.3	.3	.1 .5	5.0 12.5
17-Jun 11	0		XX	1.8		3.31	.3	1.7	1.7	.3	.3	.1 .5	5.0 12.5
17-Jun 11	40		XX	1.8									12.5
17-Jun 15	0		XX	2.0	4	2.53	.1	.4	.2	.1		.1 .9	12.6

## TERRA VAC/ ECC - ERM SITE / PROJECT 88-304

[illegible]

**APPENDIX B**

TEHERA VAC/ ECC - ERM SITE / PROJECT 88-304

II																					
II HORIZONTAL EXTRACTION WELL - REV-2										REV-2											
II																					
SAMPLE TIME		(( OPERATION DATA ))					(( GAS CHROMATOGRAPH READOUT ))							(( WELLHEAD CONCENTRATION ))							
		INJ	WELL	FLOW	FLOW		1,1	1,1,1	M.P- TOTAL					1,1	1,1,1	M.P-					
		SAMP	VOL	VAC	RATE	RATE	DCE	TCA	TCE	TOL	PCE	XYL	AREA		DCE	TCA	TCE	TOL	PCE	XYL	OTHER
DATE	HRS MIN	II	NUM	(ml)	(in)	(SCFM)	(ACFM)	(ng/l)	(ng/l)	(ng/l)	(ng/l)	(ng/l)	(ng/l)	1000X	(ng/l)	(ng/l)	(ng/l)	(ng/l)	(ng/l)	(ng/l)	(ng/l)
=====																					
14-Jun	12 17	II	777										0								
14-Jun	12 18	II	106	100	10.0	4	5	.163	1.170	1.150	.094	.200	.019	1020		2.445	17.55	17.25	1.410	3.000	.265 7.92
14-Jun	12 38	II	107	100	10.0	4	5	.146	1.850	.863	.121	.109	.024	1105		2.190	28.35	12.95	1.815	1.955	.360 8.27
14-Jun	13 18	II	108	100	10.0	4	5	.162	1.870	.791	.129	.132	.031	930		2.430	26.05	11.67	1.935	2.445	.465 5.31
14-Jun	13 31	II	959	100	10.0	4	5														
14-Jun	14 31	II	777	100	10.0	4	5														
14-Jun	15 31	II	109	100	7.5	4	5	.128	2.216	.903	.171	.131	.048	990		1.707	29.55	12.04	2.260	2.367	.640 3.94
14-Jun	15 40	II	959	100	8.0	4	5														
14-Jun	16 29	II	777	100	9.0	4	5														
14-Jun	17 29	II	110	100	8.5	8	10	.103	1.953	.915	.182	.138	.057	928		1.437	27.25	12.77	2.540	2.721	.755 3.55
14-Jun	20 42	II	111	100	9.0	8	10	.077	1.328	.823	.152	.130	.051	728		1.100	18.97	11.76	2.171	2.566	.729 2.78
15-Jun	8 39	II	959	100	9.3	17	20														
15-Jun	9 20	II	777	100	9.0	17	20														
15-Jun	11 30	II	112	100	9.0	17	20	.046	.724	.626	.104	.104	.036	475		.657	10.34	8.94	1.466	2.000	.514 1.76
15-Jun	12 10	II	888	100	10.0	16	20														
15-Jun	12 23	II	888	100	10.0	16	20														
15-Jun	12 27	II	888	100	9.0	17	20														
15-Jun	14 50	II	888	100	8.5	17	20														
15-Jun	15 55	II	117	100	9.5	17	20	.036	.520	.491	.077	.084	.025	358		.527	7.610	7.165	1.127	1.555	.366 1.39
15-Jun	16 2	II	888	100	8.5	25	30														
16-Jun	10 48	II	888	100	9.0	33	40														
16-Jun	13 6	II	120	100	9.1	38	45	.020	.266	.283	.042	.051	.012	191		.287	3.818	4.062	.603	.904	.172 .66
16-Jun	15 45	II	888	100	9.0	38	45														
16-Jun	16 30	II	959	100	1.0	44	45														
16-Jun	19 15	II	777	100	12.0	54	70														
17-Jun	10 45	II	125	100	7.8	106	123	.014	.134	.162	.021	.034	.007	143		.189	1.811	2.189	.264	.554	.095 .93
17-Jun	11 0	II	959	100	1.0	0															
17-Jun	11 40	II	777	100	1.0	0															
17-Jun	15 0	II	129	100	9.0	115	138	ND	.060	.081	.011	.018	.003	50		.857	1.157	.157	.300	.043 .18	



[illegible]





TEERA VAC/ ECC - ERM SITE / PROJECT 88 - 304

----- IX -----																							
IX VERTICAL EXTRACTION WELL - VE-1												VERTICAL EXTRACTION WELL - VE-1											
----- IX -----																							
SAMPLE TIME		(( OPERATION DATA ))				(( GAS CHROMATOGRAPH READOUT ))								(( WELLHEAD CONCENTRATION ))									
		INJ WELL FLOW FLOW				M,P- TOTAL								M,P-									
		SIEP VOL VAC RATE RATE				DCE TCA TCE TOL PCE XYL AREA								DCE TCA TCE TOL PCE XYL OTHER									
DATE	ERS MIN	IX	NUM	(ml)	(°Hg)(SCFH)	(ACFH)	(ng/l)	(ng/l)	(ng/l)	(ng/l)	(ng/l)	(ng/l)	1000X	(ng/l)	(ng/l)	(ng/l)	(ng/l)	(ng/l)	(ng/l)	(ng/l)	(ng/l)	(ng/l)	
=====																							
14-Jun 12	17	IX											0										
14-Jun 12	18	IX		100	1.0								0										
14-Jun 12	36	IX		100	1.0								0										
14-Jun 13	16	IX		100	1.0								0										
14-Jun 13	31	IX		100	1.0								0										
14-Jun 14	31	IX		100	1.0								0										
14-Jun 15	31	IX		100	1.0								0										
14-Jun 15	40	IX		100	1.0								0										
14-Jun 16	29	IX		100	1.0								0										
14-Jun 17	29	IX		100	1.0								0										
14-Jun 20	42	IX		100	1.0								0										
15-Jun 8	39	IX		100	1.0								0										
15-Jun 9	20	IX		100	1.0								0										
15-Jun 11	30	IX		100	1.0								0										
15-Jun 12	10	IX	777	100	8.8								0										
15-Jun 12	23	IX	113	100	9.0	4	511	.606	1.501	2.584	.059	.267	.007	1049	11	8.657	21.44	36.91	.843	3.814	.160	1.25	
15-Jun 12	27	IX	888	100	8.8	4	511								11								
15-Jun 14	50	IX	116	100	9.0	4	511	.078	.762	.558	.072	.082	.020	490	11	1.114	11.17	7.97	1.029	1.171	.286	2.62	
15-Jun 15	55	IX	888	100	9.0	8	1011								11								
15-Jun 16	2	IX	888	100	9.0	6	1011								11								
16-Jun 10	48	IX	888	100	8.5	13	1511								11								
16-Jun 13	6	IX	121	100	8.0	13	1511	.608	.065	.030	.016	.008	.003	61	11	.109	.69	.41	.216	.109	.041	.40	
16-Jun 15	45	IX	888	100	1.0	15	1511								11								
16-Jun 16	30	IX	999	100	1.0	15	1511								11								
16-Jun 19	15	IX	777	100	1.0	15	1511								11								
17-Jun 10	45	IX	126	100	8.8	17	2011	.016	.641	.082	.012	.015	.003	68	11	.226	1.15	1.16	.170	.212	.642	.36	
17-Jun 11	0	IX	999	100	1.0		11								11								
17-Jun 11	40	IX	777	100	1.0		11								11								
17-Jun 15	0	IX	128	500	10.0	4	511	.053	.339	.213	.070	.041	.017	280	11	.159	1.02	.64	.210	.123	.051	.33	

TEERRA VAC/ ECC - ERM SITE / PROJECT 88 - 304

----- XX -----																							
XX VERTICAL EXTRACTION WELL - VE-1												VERTICAL EXTRACTION WELL - VE-1											
----- XX -----																							
SAMPLE TIME				(( OPERATION DATA ))				(( GAS CHROMATOGRAPH READOUT ))				(( WELLHEAD CONCENTRATION ))											
				INJ WELL FLOW PLOT				M.F- TOTAL				M.F-											
				XX SAMP VOL VAC RATE RATE				DCE TOL TCE TOL PCE TOL AREA				DCE TOL TCE TOL PCE TOL PCE TOL OTHER											
DATE	HRS	MIN	XX	NUM	(ml)	(°Eq)(SCFM)	(ACFM)	(ng/l)	(ng/l)	(ng/l)	(ng/l)	(ng/l)	(ng/l)	1000X	(ng/l)	(ng/l)	(ng/l)	(ng/l)	(ng/l)	(ng/l)	(ng/l)	(ng/l)	(ng/l)
=====																							
18-Jun 10	0		XX	132	500	7.8	4	511	.049	.339	.215	.061	.044	.016	256	11	.132	.92	.58	.165	.119	.043	.25
19-Jun 10	30		XX	135	500	7.1	4	511	.038	.424	.256	.055	.048	.017	256	11	.100	1.11	.67	.144	.126	.045	.36
19-Jun 10	47		XX	999	100	1.0		11								11							
19-Jun 11	40		XX		100	1.0		11								11							
20-Jun 9	20		XX		100	1.0		11								11							
20-Jun 9	50		XX		100	1.0		11								11							
20-Jun 10	35		XX		100	1.0		11								11							
20-Jun 15	0		XX		100	1.0		11								11							
21-Jun 9	0		XX		100	1.0		11								11							
21-Jun 9	33		XX		100	1.0		11								11							
21-Jun 10	30		XX	777	100	1.0		11								11							
22-Jun 10	0		XX	140	500	14.6	4	511	.094	.568	.692	.047	.101	.017	364	11	.366	2.29	2.70	.183	.394	.066	.56
22-Jun 16	10		XX	145	500	14.4	4	511	.081	.663	.690	.057	.124	.022	415	11	.312	2.55	2.65	.219	.477	.085	.48
23-Jun 10	0		XX	146	500	14.5	4	511	.095	.699	.656	.071	.136	.032	556	11	.368	3.48	3.31	.275	.526	.124	.60
24-Jun 11	0		XX	154	500	14.5	4	511	.019	.262	.211	.017	.033	.009	135	11	.074	.78	.82	.066	.128	.035	.20
24-Jun 14	30		XX	999	500		5	511								11							
24-Jun 16	34		XX	777	500	10.0	4	511								11							
24-Jun 16	50		XX	668	500	8.7	4	511								11							
24-Jun 17	35		XX	668	500	8.9	4	511								11							
25-Jun 9	15		XX	999	500	8.0	4	511								11							
25-Jun 10	30		XX	777	500	8.0	4	511								11							
27-Jun 11	30		XX	160	500	6.8	4	511	.026	.437	.290	.069	.041	.036	277	11	.067	1.13	.75	.178	.106	.093	.22
27-Jun 11	45		XX	999	500	6.8	4	511								11							
27-Jun 16	0		XX		500	6.8	4	511								11							
28-Jun 10	35		XX		500	6.8	4	511								11							
29-Jun 10	0		XX		500	6.8	4	511								11							
30-Jun 9	15		XX		500	6.8	4	511								11							
06-Jul 11	0		XX		500	6.8	4	511								11							
13-Jul 11	0		XX		500	6.8	4	511								11							
20-Jul 10	40		XX		500	6.8	4	511								11							

**ATTACHMENT 1**

## TERRA VAC CORPORATION

Project 88-304

Gas Chromatograph ParametersI. SCOPE

In order to accurately quantitate Volatile Organic Compound (VOC) content it is necessary to insure peak separation. This is achieved by the use of an appropriate column, with the aid of a temperature program. The parameters for this program are set forth here.

II. EQUIPMENT AND REAGENTS

1. Clean and well lighted work area
2. Temperature programmable gas chromatograph (Shimadzu GC-9A) equipped with a flame ionization detector (FID) and a wide bore capillary column.
3. Nitrogen, carrier gas, zero grade or better
4. Hydrogen, combustion gas, zero grade or better
5. Air, combustion gas, zero grade or better

III. PARAMETERS

1. Initial temperature, 40 C
2. Initial hold, 2 minutes
3. Program rate, 5 C/minute
4. Intermediate temperature, 85 C
5. Intermediate hold, 0.5 minutes
6. Secondary ramp rate, 15 C/minute
7. Final temperature, 150 C
8. Final hold, 3 minutes
9. Inlet temperature, 150 C
10. Carrier gas flow, 20 ml/minute
11. Combustion gas flow, Air, 350 ml/minute
12. Combustion gas flow, Hydrogen, 55 ml/minute
13. Detector range, 10<sup>-1</sup>

IV. PRECAUTIONS

Do not exceed temperature limit of column. Do not operate oven without oven fan operating. Periodically check and clean air filter to electronics. Technician must be fully trained before attempting to operate the gas chromatograph.

**ATTACHMENT 2**

## TERRA VAC CORPORATION

Project 88-304

Integrator ParametersI. SCOPE

The parameters stated here are normal operating parameters for use with a flame ionization detector (FID). These parameters will require periodic optimization by the operator in order to achieve maximum sensitivity.

II. EQUIPMENT AND REAGENTS

1. Clean and well lighted work area
2. Integrator (Shimadzu C-R3A)

III. PARAMETERS

1. Zero = 0
2. Attenuation (ATTN 2 ) = 4
3. Chart speed (CHT SP) = 10 mm/min.
4. Area reject (AR REJ) = 250
5. Slope = 300

IV. PRECAUTIONS

It is important that the operator has a full understanding of the instrument in order to achieve optimization. If in doubt about any procedure, refer to the operation manual.



**ATTACHMENT 3**

TERRA VAC CORPORATION

Project 88-304

Sampling Techniques of Volatile Organic Compounds

I. SCOPE

Volatile Organic Compounds (VOC) are regulated, toxic chemicals and should be treated with care to avoid personal and environmental contamination.

When sampling vapors from the vacuum system it will be considered that the air stream is contaminated with VOC's.

II. EQUIPMENT AND REAGENTS

1. Clean and well lighted work area
2. Hamilton Gastight Syringes 1000ul, 500ul, 250ul sizes

III. PROCEDURE

1. Purge syringe with clean air
2. Insert syringe into well head septum
3. Purge syringe with air stream to be sampled
4. Draw plunger back to desired volume
5. Withdraw needle from wellhead septum and stopper with a septum
- 6 Log time, location, wellhead vacuum and flow then return sample to GC

IV. PRECAUTIONS

Test syringe before use for leaking plunger and tight needle.

**ATTACHMENT 4**

## TERRA VAC CORPORATION

Project 88-304

Volatile Organic Compounds StandardI. SCOPE

The purpose of this procedure is to define the standardization of the gas chromatograph for reference in the quantitative analysis of samples containing unknown amounts of Volatile Organic Compounds.

II. EQUIPMENT AND REAGENTS

1. Clean and well lighted work area
2. Gastight syringes 1000ul, 250ul, 100ul.
3. Pure compounds (CAUTION: Some VOC's are known carcinogens and should be handled with care to avoid possible contamination.)
4. Gas sampling bulb 1000ml size

III. PROCEDURESCalibration using pure VOC to make gas standard

1. Run a blank of the syringe and 1 liter gas sampling bulb to be used.
2. Inject a known volume of the liquid VOC (or of an equal volume mixture of several compounds of interest) into the 1 liter bulb (verify actual bulb volume beforehand). This is on the order of 1 ul for 100 to 300 ppm levels.
3. Allow the liquid to vaporize and disperse throughout the bulb. This may take 5-10 minutes depending on volatility of the compounds. See precautions.
4. Using a gastight syringe, withdraw a 100-1000ul sample from the bulb and inject it into the GC. Volume utilized should approximate expected field concentrations.
5. Calculation of concentration:

$$\text{mg/L} = \frac{\text{sp.gravity} * \text{liq.vol} * \% \text{purity} * \text{inj.volume (ul)}}{\text{bulb volume} * 100\% * 1000\text{ul}}$$

6. If not within 10% of previous calibration, repeat 4&5. Otherwise maintain calibration values established.
7. Calibrate to new values when repeatability is shown. See precautions.

#### IV PRECAUTIONS

1. In injecting headspace vapor from pure compound, care must be taken not to overload the column.
2. A wide change in calibration values indicates that troubleshooting of the system or procedures is necessary.
3. In using a liquid, be sure the volume injected will be well below vapor saturation for the bulb volume used.
4. Examine the bulb for any droplets or condensation that may indicate incomplete vaporization of the liquid. Some warming of the bulb (i.e., sunlight, rubbing with a cloth, even the GC oven briefly) may hasten the process. The less volatile the compound, the more problem this becomes.
5. Do not rely on the bulb's integrity for more than an hour.

**APPENDIX B**

**ECC REMEDIAL ACTION PLAN  
ESTIMATION OF WATER VOLUMES COLLECTED  
IN THE GROUND WATER INTERCEPTION TRENCH**

## APPENDIX B

### ECC REMEDIAL ACTION PLAN ESTIMATION OF WATER VOLUMES COLLECTED IN THE GROUND WATER INTERCEPTION TRENCH

Following the procedure in Appendix B of the FS:

$$Q_t = Q_r + Q_i + Q_{rec}$$

where:

$Q_t$  = total water flow to the trench, gpm

$Q_r$  = regional ground water flow to the trench, gpm

$Q_i$  = flow induced due to the presence of the trench, gpm

$Q_{rec}$  = recharge flow, due to precipitation and upward recharge from the sand and gravel unit, gpm

$$Q_r = K_r \cdot A_r \cdot i_r$$

where:

$K_r$  = permeability of till =  $10^{-5}$  cm/s = 0.212 gal/d.ft<sup>2</sup> (section 5 of RI)

$d$  = depth of trench, assume 10 ft

$A_r$  = area of trench in the direction of ground water flow, ft<sup>2</sup> =  $L \times d$

$L$  = length of trench, 330 ft

$i_r$  = regional gradient = 0.05 ft/ft south of the site (Appendix B of FS)

$$Q_i = K_i \cdot i_I \cdot A_i$$

where:

$K_i$  = permeability of till =  $10^{-5}$  cm/s = 0.212 gal/d.ft<sup>2</sup> (Section 5 of RI)

$i_i$  = gradient induced due to drain -  $h/l$

$h$  = height of water table above the drain centers  
=  $1/2$  maximum depth = 5 ft

$l$  =  $z/2$  = 20 ft

$z$  = zone of influence of trench in the perpendicular direction, 40 ft

$A_i$  = area of induced flow =  $L \times h$

$$Q_{rec} = (W_p + W_v) A_{rec}$$

where:

$W_p$  = recharge due to precipitation, assumed to be  
7.8 in/yr = 0.013 gal/d.ft<sup>2</sup> (Appendix B of FS)

$W_v$  = recharge due to upward movement from the sand and gravel unit =  $k_v \times i_v$

$k_v$  = vertical permeability of till assumed to be  
 $10^{-5}$  cm/s = 0.212 gal/d.ft<sup>2</sup>

$i_v$  = vertical gradient = 0.25 ft/ft = 3 ft difference in head over 12 ft of thickness of shallow saturated zone (Appendix B of FS)

$A_{rec}$  = recharge area, ft<sup>2</sup> -  $L \times Z$

For the trench to be installed at ECC =

$$\begin{aligned} Q_r &= 0.212 \text{ gal/d.ft}^2 \times 330 \text{ ft} \times 10 \text{ ft} \times 0.05 \text{ ft/ft} \\ &\quad \times 1 \text{ d/1440 min} \\ &= 0.03 \text{ gpm} \end{aligned}$$

$$\begin{aligned} Q_i &= 0.212 \text{ gal/d.ft}^2 \times 330 \text{ ft} \times 5 \text{ ft} \times 0.25 \text{ ft/ft} \\ &\quad \times 1 \text{ d/1440 min} \\ &= 0.06 \text{ gpm} \end{aligned}$$

$$\begin{aligned} Q_{rec} &= 0.013 \text{ gal/d.ft}^2 \times 330 \text{ ft} \times 40 \text{ ft} \times 1 \text{ d/1440 min} \\ &\quad + 0.212 \text{ gal/d.ft}^2 \times 330 \text{ ft} \times 40 \text{ ft} \times 0.25 \text{ ft/ft} \times 1 \text{ d/1440 min} \\ &= 0.61 \text{ gpm} \end{aligned}$$

$$Q_t = 0.03 + 0.06 + 0.61 = 0.70 \text{ gpm}$$